



CENTRAL AVENUE NW

13TH STREET NW

3RD AVENUE NW

13TH STREET NW

installed 1 1/2" corporation and 11/2" to 11/4" coupling

removed existing reducer

install 8" coupling

installed 8" valve

installed 8" tee

removed existing reducer

install 8" coupling

installed 8" valve

installed 8" tee

installed 8" valve

B

B

B

B

B

B

B

B

B

CONNECTED EXISTING 3/4" SERVICE LINE. INSTALL 1" SADDLE & CORPORATION, 1" COPPER PIPING AND 1" to 3/4" COUPLING, EXCEPT WHERE NOTED

** NOTE ** SIZE, NUMBER AND LOCATION OF WATER SERVICES TO BE DETERMINED AND VERIFIED IN THE FIELD

** NOTE ** A COST PER ADDITIONAL SERVICE MUST BE PROVIDED IN BID FOR WORK

** NOTE ** ASPHALT TO BE REMOVED AND REPLACED BY CITY

** NOTE ** COMPACTION OF ALL TRENCHES MUST BE ACCORDING TO CITY OF MANDAN CONSTRUCTION SPECIFICATIONS, 3 TESTS PER BLOCK AT 2 LEVELS

** NOTE ** WATERMAIN FOR THIS SHEET SHOULD BE LOCATED 8' FROM THE BACK OF CURB