

NORTH DAKOTA STATE HIGHWAY DEPARTMENT
CULVERT LIST
PROJECT NO. F-1-094(03)

<u>STATION</u>	<u>LOCATION</u>	<u>SIZE</u>	<u>LENGTH</u>	<u>ITEM</u>	<u>END SECTIONS</u>	<u>STATION</u>	<u>LOCATION</u>	<u>SIZE</u>	<u>LENGTH</u>	<u>ITEM</u>	<u>END SECTIONS</u>
50+07	Lt.	18"	50'	CSP .064"		80+20	Lt.	18"	50'	CSP .064"	
51+00	Lt.	18"	50'	CSP .064"		81+40	Rt.	18"	50'	CSP .064"	
53+00	Lt.	18"	50'	CSP .064"		82+57	Lt.	18"	50'	CSP .064"	
54+00	Rt.	18"	40'	CSP .064"		83+01.8	Lt.	58"x36" 58"x36"	32' 32'	CSP .064" CAP .135"	2-.109" 2-.105"
58+84	Rt.	18"	40'	CSP .064"		83+01.8	Ē	58"x36"	78'	RCP, Cl. II	2
60+80	Lt.	18"	50'	CSP .064"		84+80	Lt.	18"	50'	CSP .064"	
61+75	Ē	29"x18"	80'	RCP, Cl. IV	2	85+75	Lt.	18"	50'	CSP .064"	
62+25	Rt.	18"	50'	CSP .064"		85+75	Rt.	18"	40'	CSP .064"	
64+06	Lt.	18"	50'	CSP .064"		86+46	Lt.	18"	50'	CSP .064"	
65+79	Lt.	18"	50'	CSP .064"		87+89	Lt.	18"	50'	CSP .064"	
66+55	Rt.	18"	50'	CSP .064"		89+20	Lt.	18"	40'	CSP .064"	
66+55	Lt.	18"	50'	CSP .064"		90+05	Lt.	18"	50'	CSP .064"	
68+00	Rt.	18"	40'	CSP .064"		92+36	Lt.	18"	50'	CSP .064"	
68+00	Lt.	18"	50'	CSP .064"		94+00	Lt.	18"	50'	CSP .064"	
69+08	Rt.	18"	50'	CSP .064"		94+60	Lt.	18"	40'	CSP .064"	
70+61	Lt.	18"	50'	CSP .064"		95+88	Rt.	18"	50'	CSP .064"	
70+61	Rt.	18"	50'	CSP .064"		95+88	Lt.	18"	50'	CSP .064"	
73+10	Lt.	18"	50'	CSP .064"		96+73	Lt.	18"	40'	CSP .064"	
73+10	Rt.	18"	50'	CSP .064"		97+95	Lt.	18"	50'	CSP .064"	
74+56.3	Rt.	18"	60'	CSP .064"		98+48	Ē	44"x27"	80'	RCP, Cl. III	2
74+60	Lt.	18"	50'	CSP .064"		99+50	Lt.	18"	50'	CSP .064"	
76+56	Lt.	18"	50'	CSP .064"							
77+40	Lt.	18"	50'	CSP .064"							
77+40	Rt.	18"	50'	CSP .064"							
79+35	Rt.	18"	50'	CSP .064"							