

Q U A N T I T I E S

<u>SPEC.</u>	<u>CODE</u>	<u>ITEM</u>	<u>UNIT</u>	<u>QUANTITY</u>
103	0100	Contract Bond	L.Sum	1
201	0330	Clearing and Grubbing	L.Sum	1
202	0112	Removal of Concrete	S.Y.	4820
202	0130	Removal of Curb & Gutter	L.F.	29
203	0180	Roadway Obliteration	L.F.	500
203	0201	Embankment-Type A	C.Y.	107,237
216	0100	Water	M.Gal.	1,390
220	0100	Foundation Fill	C.Y.	634
302	0121	Aggregate Base Course-Cl. 5	C.Y.	331
401	0100	MC-70, 250 Liquid Asphalt	Gal.	3069
401	0152	SS-1h or CSS-1h Emulsified Asphalt	Gal.	3140
401	0160	Blotter Material-Cl. 44	Ton	230
406	0190	Hot Bituminous Pavement-Cl. 25	Ton	11,934
406	0310	85-100 Asphalt Cement	Ton	776
630	2216	12" Reinforced Concrete Pipe Sewer, Cl. III	L.F.	519
630	2256	15" Reinforced Concrete Pipe Sewer, Cl. III	L.F.	129
630	2380	24" Reinforced Concrete Pipe, Cl. III	L.F.	64
630	2381	24" Reinforced Concrete Pipe Sewer, Cl. III	L.F.	1269
630	2426	27" Reinforced Concrete Pipe Sewer, Cl. III	L.F.	1180
630	2465	30" Reinforced Concrete Pipe, Cl. III	L.F.	136
630	2466	30" Reinforced Concrete Pipe Sewer, Cl. III	L.F.	51
630	2472	30" Reinforced Concrete Pipe Sewer, Cl. IV	L.F.	168
630	2736	60" Reinforced Concrete Pipe Sewer, Cl. III	L.F.	316
630	3086	22"x13" Reinforced Concrete Pipe Arch Sewer Cl. III	L.F.	72
630	3255	12" Reinforced Concrete End Section	Ea.	1
630	3275	24" Reinforced Concrete End Section	Ea.	1
630	3285	30" Reinforced Concrete End Section	Ea.	5
630	3330	22"x13" Reinforced Concrete Arch End Section	Ea.	2
705	0100	Mobilization	L.Sum	1
708	0290	72" Valley Gutter-Type I	S.Y.	336
708	0300	Curb & Gutter-Type I	L.F.	8117
712	0100	Concrete Sidewalk	S.Y.	920
712	0110	Concrete Driveway	S.Y.	197
714	0110	48" Manhole Riser	L.F.	28
714	0120	60" Manhole Riser	L.F.	67
714	0124	84" Manhole Riser	L.F.	12
714	0130	Inlets	Ea.	6
714	0134	Double Inlets	Ea.	5
714	0135	Triple Inlets	Ea.	1
714	0208	48" Manhole	Ea.	5
714	0212	60" Manhole	Ea.	5
716	0110	Adjust Manhole	Ea.	12
716	0140	Adjust Utility Apportenances	Ea.	15
726	0300	Seeding-Type E, Cl. Iv	Acre	13
728	0100	Sodding	S.Y.	172
730	0100	Mulching-Method A	Acre	12